



भारतीय भूमि पत्तन प्राधिकरण

गृह मंत्रालय, भारत सरकार

Land Ports Authority of India

Ministry of Home Affairs Government of India

अवर सचिव ऑपरेशन))

भारतीय भूमि पत्तन प्राधिकरण, लोक नायक

भवन खान मार्केट नई दिल्ली-110003

फोन नंबर :-011-24340714

Office of Under Secretary (Operation-2)

Land Ports Authority of India, Lok Nayak

Bhawan Khan Marker New Delhi-110003

Phone No:- 011-24340714

File NO. OPS/30028/618/MISC/CAMC/2025/Dawki(E)(3734446)

Dated: Sept, 2026

NOTICE INVITING QUOTATION

SUBJECT: - CONSTRUCTION OF RCC RAMP LENGTH EXTENSION FOR 120 MT WEIGH BRIDGE AT LAND PORT DAWKI.

Sealed item rate quotations are hereby invited on behalf of the Chairman, Land Ports Authority of India (LPAI) from eligible and experienced agencies/contractors for the following work:

Sl. No	Name of Work	Estimated Cost including all taxes	Time of Completion
1	CONSTRUCTION OF RCC RAMP LENGTH EXTENSION FOR 120 MT WEIGH BRIDGE AT LAND PORT DAWKI	₹8,12,113/-	30 Days
	(Rupees Eight Lakh Twelve Thousand One Hundred Thirteen only) including all taxes		

1. Eligibility Criteria:

The intending quotationers/contractors should fulfill the following eligibility conditions:

1. The contractor should have experience of executing similar nature of civil works / RCC work in Building / RCC work in culvert / RCC work in Road of estimate amount of similar nature of work of 80% 01 work / 60% 02 works / 40 % 03 works of estimated cost of during last 3 years and submit the Awarding work Letter and Completion certificate of said work.
2. The contractor should possess valid:
 - o PAN Card
 - o GST Registration
 - o Bank Account Details
3. The agency should not have been blacklisted/debarred by any Government Department/PSU/Autonomous Body.

2. Scope of Work

The work mainly includes Civil Work:

- Earth Work
- Filling available excavated Earth
- Providing Laying Cement Concrete
- Reinforce Cement concrete
- Structural Steel Work
- Finishing and miscellaneous works complete as per direction of Under Secretary Operations-II / Engineer-in-Charge.

3. Availability of NIQ Documents

The quotation documents can be obtained from the office of the Under Secretary Operations-II, Land Port Authority of India, HQ, Lok Nayak Bhawan, B-Wing, 1st Floor, Khan Market, New Delhi during office hours from 16/09/2026 to 28/09/2026.

4. Submission of Quotations

1. The quotation shall be submitted in sealed cover superscribing:
"CONSTRUCTION OF RCC RAMP LENGTH EXTENSION FOR 120 MT WEIGH BRIDGE AT LAND PORT DAWKI"
2. The quotation shall be addressed to:

To,

Under Secretary, Operation-II
Land Ports Authority of India
Lok Nayak Bhawan, B-Wing, 1st Floor,
Khan Market, New Delhi

3. Last date and time of submission: 28/09/2026 up to 3:00PM.
4. Quotations received after due date and time shall not be entertained.

5. Opening of Quotations

The quotations will be opened on 28/09/2026 at **03:30 PM** in the office of the Under Secretary Operations-II, HQ, Land Port Authority of India in presence of quotationers or their authorized representatives who wish to attend.

6. Terms & Conditions

1. The rates shall be quoted inclusive of all taxes, duties, labour charges, transportation, loading/unloading, tools & plants, and all incidental charges.
 2. GST shall be applicable as per prevailing Government rules.
 3. The work shall be executed as per CPWD specifications and directions of Under Secretary Operations-II / Engineer-in-Charge.
 4. The contractor shall complete the work within stipulated time period of 30 days from the date of issue of work order.
 5. No escalation on any account shall be entertained during the contract period.
 6. Necessary safety measures shall be ensured by the contractor during execution of work.
 7. The agency shall be fully responsible for quality and workmanship of the work executed.
- 

8. Measurement of work shall be recorded jointly and payment shall be released based on actual work executed.
9. LPAI reserves the right to accept or reject any or all quotations without assigning any reason thereof.
10. Conditional quotations shall be summarily rejected.

7. Documents to be submitted

The following documents shall be submitted along with quotation:

- Copy of PAN Card
- Copy of GST Registration Certificate
- Experience Certificate of similar nature of work of 80% 01 work / 60% 02 works / 40 % 03 works of estimated cost of during last 3 years in the government department / PSUs / Autonomies Body / reputed company.
- Signed copy of NIQ document as token of acceptance of terms & conditions.

8. Defect Liability Period

The defect liability period shall be 12 months from the date of completion of work.



(Ranjit Kumar)

Under Secretary (Operations-II)

Tele: 011-24340714

Copy to:

- (i) **The Manager Land Port, Dawki
Notice Board,**
- (ii) **LPAI Web Site**

ANNEXURE – II

Bidder Information Sheet

Sl. No.	Particulars	Details to be Filled by Bidder
1	Name of Agency/Contractor	
2	Registered Address	
3	Contact Number	
4	Email ID	
5	Name of Authorized Signatory	
6	PAN Number	
7	GST Registration Number	
8	Bank Account Number	
9	Name of Bank	
10	IFSC Code	
11	Experience in Similar Works	
12	Blacklisted / Debarred Status (Yes/No)	

Date: _____

Place: _____

Signature of Bidder
With Seal and Stamp

ANNEXURE – III

Financial Quotation

Sl. No.	Description of Work	Amount (₹) (Inclusive of all taxes & GST)
1	CONSTRUCTION OF RCC RAMP LENGTH EXTENSION FOR 120 MT WEIGH BRIDGE AT LAND PORT DAWKI	

Total Quoted Amount (in words):

Date: _____

Place: _____

Signature of Bidder
With Seal and Stamp

ANNEXURE – IV

Declaration / Undertaking by Bidder on the Letter Head

I/We hereby declare that:

1. I/We have not been blacklisted or debarred by any Government Department/PSU/Autonomous Body.
2. I/We accept all terms and conditions of the NIQ without any deviation.
3. I/We have understood the scope of work and site conditions.
4. The information furnished is true and correct.
5. I/We shall execute the work strictly as per specifications and directions of the Engineer-in-Charge.

Date: _____

Place: _____

Signature of Bidder
With Seal and Stamp

Annexure - I

ABSTRACT OF WEIGHT BRIDGE RAMP FOUNDATION & EXISTING WEIGHT BRIDGE STEEL SECTION FOR RAMP

Sl no.	Description of work	Unit		Qty	Amount	Remark
	EARTH WORK					
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50m and lift upto 1.5m, as directed by Engineer-in- charge.					
	-	cum	177.5	36.575	6492.06	
2	All kinds of soil					
	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	196	17.6	3449.60	
	CONCRETE WORK					
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level					
	: 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size).	cum	6812	5.035	34298.42	
	REINFORCED CEMENT CONCRETE					
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :					
	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	9045.75	19.70	178185.44	
	FORMWORK					
5	Centering and shuttering including strutting, propping etc. and removal of form for all heights :					
	Foundations, footings, bases of columns, etc. for mass concrete.	sqm	392.15	13.15	5156.77	
	STEEL REINFORCEMENT					
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
	Mechanically Treated bars of grade Fe-500 D or more	kg	107.85	887.57	95724.00	
7	Structural steel work riveted, bolted or welded in build up section, truss and framed work, including cutting hoisting, fixing, in position and apply a priming coat of approved steel prime all complete. (ISMB 200)	KG	968	133.7	129421.60	

8	Structuural steel work riveted, bolted or welded in build up section ,trus and framed work ,including cutting hoisting ,fixing,in position and apply a priming coat of approved steel prime all complete (ISMC- 150)	KG	2688	133.7	359385.60	
					812113.50	
	Amount					



Ranjit Kumar
Under Secretary OPS- II
LPAI, HQ